

ARCH BRIDGE WITH MODULAR BLOCK WING WALLS

**Arch Bridge with Modular Block
Wing Walls, Per NYSDOT 554
Specification:**

**Project: Youngstown-Wilson
Rd. Bridge**

Location: Youngstown, NY

Owner: Niagara Co. DPW

**Engineer: C & S Engineers
& Niagara Co. DPW**

**Contractor: Mark Cerrone, Ni-
agara Falls , NY**

**Unique features: Redi Rock
Wing Walls**

**Arch Bridge Structures are avail-
able from 12' 0" Span up to
60'0"+. Call our Engineering
Team with your product specific
issues.**



**Sections of 28'-0" Span 22 Tons Arched Culvert sections, per AASH-
TO HL-93 Loading. Detached precast headwalls.**

**One set of Precast anchor style flat Wing walls & one set of Segmen-
tal Precast Big Block NYSDOT Sec. 554-01 Approved wall system to
accommodate & eliminating the delay of construction for wire reloca-
tion & allowing install under low overhead wires.**